WCESD# 4
Fire Alarm Process Flow

```
┌─────────────────────┐
│   SFMO Licensed     │
│    Fire Alarm       │
│ Contractor Chosen   │
└─────────────────────┘
          │
          ▼
┌─────────────────────┐
│  Submit Plans for   │
│   Approval and      │
│     Permit          │
└─────────────────────┘
```

Revise and Resubmit Plans ◄── **No** ── (Plans Approved)

Yes

┌─────────────────────┐
│ Begin System   │
│   Installation   │
└─────────────────────┘

┌─────────────────────┐
│ Begin System   │
│   Inspections   │
└─────────────────────┘

Correct Problem and call for re-inspection ◄── **No** ── (Inspection Pass)

Yes

┌─────────────────────┐
│   Fire Alarm   │
│   Final   │
└─────────────────────┘

Audible/Visual Device(s)
↓
Initiating Device(s)
↓
Water flow
↓
Central Station Monitoring
↓
Device Address Test

Horn/Strobe above FDC shall operate on waterflow only.

Waterflow activation shall annunciate as a waterflow alarm.

Addressable device designation and location required

NOTE:
The CSM shall differentiate between types of alarms. "General Alarm" is not permitted.
(waterflow alarm, smoke detector, pull station etc…)